Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Project Division Dasarahalli Zone

**Name of Work:Formation of Playground and Providing drainage system for disposal of Rain water in and around the playground outdoor stadium ward No-14**

**Schedule-B**

| Sl No | Description of Item | Unit | Quantity | Rate, Rs | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete asper specifications.MORTH / Chapter 3( I No-19.1, P No-133)5km lead= 68+2.5x1.28x15 = 82.08 | Cum | 506.20 | 202.92 | Rupees Two Hundred Two And Paise Ninety Two Only |
| 2 | KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms^thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No. KBS 4.1, 4.2.(P.No-12,I No-4.2) | Cum | 75.93 | 5348.76 | Rupees Five Thousand Three Hundred Forty Eight And Paise Seventy Six Only |
| 3 | KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2(P.No-15,I No-4.31) | Sqm | 1351.20 | 310.58 | Rupees Three Hundred Ten And Paise Fifty Eight Only |
| 4 | Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete Cum (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing , mainand secondary beams with all lead and lifts etc., complete (exclusiveof cost of steel and fabrication charges.) (P.No-18,I No-4.48) | Cum | 204.04 | 6231.74 | Rupees Six Thousand Two Hundred Thirty One And Paise Seventy Four Only |

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

EXECUTIVE ENGINEER (Project)
Project Division
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Zone, Bangalore-73.



Scanned by CamScanner

## Schedule-B

| Sl No | Description of Item | Unit | Quantity | Rate, Rs | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 5 | KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 (P.No-17,I No-4.46.3). | Tn | 10.20 | 75275.90 | Rupees Seventy Five Thousand Two Hundred Seventy Five And Paise Ninety Only |
| 6 | Providing and Fixing RCC pre cast covering Slab of 100mm thick for drains in cement concrete M20 using graded grinite jelly 20mm and down size with steel reinforcement, including from work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in charge. (Data Rate) | Sqm | 493.20 | 1957.00 | Rupees One Thousand Nine Hundred Fifty Seven Only |
| 7 | Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge(Data Rate) | Sqm | 12.00 | 4931.00 | Rupees Four Thousand Nine Hundred Thirty One Only |
| 8 | Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete(P.No. 25, I.No. 5.30) | Nos | 1240.00 | 331.78 | Rupees Three Hundred Thirty One And Paise Seventy Eight Only |
| 9 | KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8(P.No. 182, I.No. 24.1) | Sqm | 195.30 | 63.60 | Rupees Sixty Three And Paise Sixty Only |

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

EXECUTIVE ENGINEER (Project)
Project Division
Bruhat Bangalore Mahanagara Palike,

Scanned by CamScanner

## Schedule-B

| Sl. No. | Description of Item | Unit | Quantity | Rate, Rs | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 10 | Earth work for lowering and levelling the ground other than foundation works by mechanical means upto 3.00 depth, including providing shoring and strutting, removal of stumps and other deleterious matter, dressing of sides and bottom, filling back the excavation earth to the extent required including the cost of labour & HOM of machineries, as per drawing and technical specification. | Cum | 6146.08 | 72.08 | Rupees Seventy Two And Paise Eight Only |
| 11 | KSRRB 300-Compaction KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. MORTH / Chapter 3(P.No. 149, I.No. 19.64) | Sqm | 17560.24 | 5.30 | Rupees Five And Paise Thirty Only |
| 12 | KSRRB M300- Construction of Embankment with Material Gravel/ Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density)45km lead= 2.5x1.28x45 = 82.08 | Cum | 5794.88 | 464.12 | Rupees Four Hundred Sixty Four And Paise Twelve Only |

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

EXECUTIVE ENGINEER (Project)
Project Division
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Zone, Bangalore-73.

Scanned by CamScanner

## Schedule-B

| No. | Description of Item | Unit | Quantity | Rate, Rs | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 13 | Fabricating, providing and erecting in position of MS Hot Dip Galvanised Sq. Hallow Poles of 132 X 132 Heavy gauge of length 3000mm with MS. Hot dip Galvanised grill work as per approved design and drawing of chief architect. Using 12 X 75mm galvanised flat for alround frame and 20 X 20mm galvanised forged design with square for vertical at 150mm c/c as shown in the drawing including providing forged ornamental arrowhead at top and bottom. The work is inclusive of throughing flat, square rods, placing welding all the joints, including grinding, finishing 2 coats of anticorrosive paint over one coat of metal primer. The rate is inclusive of all materials like MS. Hollow galvanized pipe, flats, forged square rods, cost of labour for all items of work cost painting, welding, cutting, grinding with all lead and lift as per specification including loading and unloading with cost and conveyance of all materials, labour, machinery andincidental charges for the successful completion of the work as per the direction of the Engineer-in-charge of the work. (Data Rate) | Sqm | 64.50 | 9144.14 | Rupees Nine Thousand One Hundred Forty Four And Paise Fourteen Only |
| 14 | Providing and fixing to wall, ceiling and floor unplasticised PVC pipes 10.00 kgf/sq.cm working pressure chemp plast / Wavin or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials,with 280mm outer dia(P.No. 75, I.No. 11.56.8) | mtr | 28.00 | 4549.52 | Rupees Four Thousand Five Hundred Forty Nine And Paise Fifty Two Only |

CUTIVE ENGINEER-4
IDL, BBMP DIVISION
ENGALURU-560 010

EXECUTIVE ENGINEER (Project)
Project Division
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Zone, Bangalore-73.

Scanned by CamScanner